

BitAffix Deployment Document Debian/Ubuntu

Initially, I checked whether MySQL or MariaDB was installed on my system using the commands:

- **mariadb --version**
- **mysql --version**

These commands indicated whether the database was installed or not.

If (not) I proceed to install MariaDB. I followed these steps

- **sudo apt update**
- **sudo apt install -y mariadb-server**
- **sudo systemctl start mariadb**
- **sudo systemctl enable mariadb**
- **sudo systemctl status mariadb**
- **sudo mariadb -u root -p**

Finally, I confirmed the installation with:

- **mariadb --version**

Next , I installed Nginx using command:

- **sudo apt install -y nginx**

To start and enable nginx service:

- **sudo systemctl start nginx**
- **sudo systemctl enable nginx**

To check nginx status

- **sudo systemctl status nginx**

Next, I attempted to run the following command in the terminal:

- **apt-get update \ \&\& apt-get install tesseract-ocr -y \ imagemagick -y \ python3 \ python3-pip \ \&\& apt-get clean \ \&\& apt-get autoremove**

If permission error, try above command using **sudo**

Then I check python3 installed or not by using the command:

→ **Python3 or python**

If (not installed) I run following command to install python3

→ **sudo apt install -y python3**

Then I tried to install Python packages using:

→ **Python3 -m pip install pyzbar \ Pillow \ Pdf2image**

To install Tesseract, I ran:

→ **apt-get install -y tesseract-ocr-ara \ && sed -i '/disable ghostscript format types/,+6d' /etc/ImageMagick-6/policy.xml**

I also installed additional dependencies:

→ **sudo apt install -y poppler-utils libzbar0**

For Node.js and npm setup, I initially tried:

→ **sudo apt-get update**
→ **sudo apt-get -y install curl gnupg**
→ **curl -sL https://deb.nodesource.com/setup_18.x | sudo -E bash -**
→ **sudo apt-get -y install nodejs**
→ **npm install --loglevel=error**
→ **sudo npm install -g pm2**

Finally, I installed LibreOffice:

→ **sudo apt-get -y install libreoffice**

Then I verify requirements:

→ **mariadb --version = mysql Ver 15.1 Distrib 10.6.14-MariaDB**
→ **node >= 18.0.0**
→ **Python3**
→ **sudo systemctl status nginx = active (running)**

Nginx Configuration on Html File

I first checked whether Nginx was installed on my system using the command:

→ **nginx -v**

Next, I created the web root directory and an HTML file:

→ **sudo mkdir -p /var/www/my_site**
→ **sudo nano /var/www/my_site/index.htm**

After that, I created a new site configuration file at:

→ **/etc/nginx/sites-available/my_site**

I added the following configuration inside the file:

```
→ server {  
→     listen 80;  
→     server_name mysite.com www.mysite.com;  
  
→     root /var/www/my_site;  
→     index index.html;  
→     location / {  
  
        try_files $uri $uri/ =404;}  
  
}
```

Then, I enabled the site and reloaded Nginx using these commands:

→ **sudo ln -s /etc/nginx/sites-available/my_site /etc/nginx/sites-enabled/**
→ **sudo nginx -t**
→ **sudo systemctl reload nginx**

